

2 030546

10-13-87

024

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-23,204-00-00

SW NE NW, SEC. 11, T 26 S, R 3 XX E

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6561

Lease Name Stareck Well # 1

Operator: Crest Petroleum, Inc.

County Butler 89.64

Name & Address Box 445

Well Total Depth 2758 feet

Andover, KS 67002

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor McAllister Drilling Co., Inc. License Number 5108

Address Wichita, KS 67202

Company to plug at: Hour: 4:00 Day: 13 Month: 10 Year: 19 87

Plugging proposal received from Gene McAllister

(company name) McAllister Drilling Co., Inc. (phone)

were: Fill hole with mud, run drill pipe to 270' and spot 35 sxs cement. Pull drill pipe to 60', spot 25 sxs cement. Pump 10 sxs in rathole.

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 08:00 Day: 13 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT Filled hole with mud, ran drill pipe to 270'. United Cementing #3797 spotted 35 sxs cement.60/40 poz. Pulled drill pipe to 60', spotted 25 sxs cement. Pulled drill pipe. Ran one joint drill pipe in rathole, pumped 10 sxs cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 15 1987

10-15-87

CONSERVATION DIVISION

Remarks: (If additional description is necessary, use BACK of this form.)

did not observe this plugging.

INVOICED

DATE 10-19-87

Signed Don Thompson (TECHNICIAN)

INV. NO. 18526