

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02010-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 33-18S-10W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BUEHLER Well #: 2
County: RICE Total Vertical Depth: 3134 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3132		125 SX
SURF	8.625	473		225 SX

101.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2008 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2008 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

RUN TUBING DOWN TO CK HOLE, OBSTRUCTION @ 2750'. CASING BELIEVED TO BE PARTED AT 745'. PERFORATE AT 1250', 900', AND 525'. RUN TUBING DOWN TO 2400 AND SAND PERFS OFF TO 2595' AND CAP WITH 10 SX'S CEMENT. PULL TUBING TO 1270' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 925' AND PUMP 35 SK'S CEMENT, PULL TUBING TO 525' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2672	2680		

INVOICED

DATE 9/15/08
INV. NO. 2009060343

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 22 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ 4% GEL. LOG TECH TICKET 24590. SWIFT SVC'C TICKET #14324. USED 325 SX'S CEMENT.

Plugged through: TBG

District: 02

Signed *Virgil Clothier*
(TECHNICIAN)

Per