

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23435-00-01
Spot: W2W2SW Sec/Twnshp/Rge: 22-12S-15W
1210 feet from S Section Line, 410 feet from W Section Line
Lease Name: VONLINTEL Well #: 2 OWWO
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		

108.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2008 8:00 AM
Plug Co. License No.: 6246 Plug Co. Name: BENNETT & SCHULTE OIL CO., A GENERAL PARTNERSHIP
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL CO., A Phone: (785) 483-2721

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 4% gel Plug thru tubing.

Plugging Proposal Received By: PAT BEDORE Witness Type: PARTIAL
Date/Time Plugging Completed: 08/21/2008 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Tried to washdown. Out of hole at 412'.
Ran sand - then 35 sxs cement.
Went back in with bit on 5 1/2" casing.
Got stuck Went in with overshot - lost overshot.
Top of fish at 323'.
Ran 10 1/2 joints of 2 7/8" - tagged up - pulled 1/2 joint.
Mixed 80 sxs cement - circulated to surface.
Pulled tubing - filled casing with approximately 10 sxs cement.

INVOICED

DATE 9-15-08
INV. NO. 2009060345

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

RECEIVED
KANSAS CORPORATION COMMISSION

Signed Ray A. Dinkel
(TECHNICIAN)

CM

AUG 26 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

AUG 22 2008

PAT

BENNETT & SCHULTE OIL CO
RUSSELL KS 67665

22-12S-15W
1210' FSL & 410' FWL, SEC

#2 VONLINTEL

site: 7-1/4 N & 2-1/4 E OF GORHAM KS
contr: ROYAL DRILLING #1

dr: RUSSELL
field: ELSASSER SW

API 15-167-23436

gsd:
fr date 05/22/2007 spd date 05/29/2007 drg comp 06/03/2007 card issued 08/13/2007 last revised 08/13/2007

ELV: 1819 GL
tops.....depth/datum
PTD.....3340 - 1521
NO TOPS RPTD

IP status:
D&A, ARB, 08/03/2007
CSG: 8-5/8" 200+ (ALT 2)
COMMENT: PROPOSED START 5/25/2007; MI & RURT
5/29/2007
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: ARB (OIL), PTD 3350 (ARB), D. & A 6/3/2007 - NO
OTHER INFO AVAILABLE - TEMP COMP 8/13/2007

COPYRIGHT 2008
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

AR 5 2008