

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19346-00-01

Spot: NENESWNE

Sec/Twnshp/Rge: 17-29S-15E

3930 feet from S Section Line, 1429 feet from E Section Line

Lease Name: CHARLEN

Well #: O10

County: WILSON

Total Vertical Depth: 249 feet

Operator License No.: 33539

Op Name: CHEROKEE WELLS LLC

Address: 4916 CP BOWIE BLVD STE 204
FT WORTH, TX 76107

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	230		
SURF	6.625	10		

35

Well Type: GSO

UIC Docket No:

Date/Time to Plug: 11/09/2007 8:00 AM

Plug Co. License No.: 33539

Plug Co. Name: CHEROKEE WELLS LLC

Proposal Rcvd. from: JEFF L. MORRIS

Company: CHEROKEE WELLS LLC

Phone: (620) 378-3650

Proposed Plugging Method: RUN 1" POLY PIPE TO BRIDGE IN HOLE AT 218'. PUMP CEMENT THRU POLY PIPE TO FILL HOLE FROM BOTTOM TO TOP. CUT OFF POLY PIPE AND LEAVE IN HOLE. AFTER CEMENT IS CURED, CUT OFF ALL PIPE APPROX. 3' BELOW GROUND LEVEL.

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 11/09/2007 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

The operator reported that the location was not accessible with a pulling unit. Therefore a 1" poly pipe was lowered down hole to 218'. The well was pumped full of cement thru this cement string. A total of 20 sacks of 60/40 poz mix with 2% gel were used to plug well. The well was cut off below plow depth.

Perfs:

Top	Bot	Thru	Comments
230	249		

INVOICED
DATE 9/15/08
INV. NO. 2009060348

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 25 2008
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #3

AUG 6 2008 AMB

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

PK