

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19355-00-01

Spot: SESWSW

Sec/Twnshp/Rge: 17-29S-15E

175 feet from S Section Line, 4105 feet from E Section Line

Lease Name: STUDEBAKER

Well #: Q16

County: WILSON

Total Vertical Depth: 236 feet

Operator License No.: 33539

Op Name: CHEROKEE WELLS LLC

Address: 4916 CP BOWIE BLVD STE 204
FT WORTH, TX 76107

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	190		
SURF	8	10		

35

Well Type: GSO

UIC Docket No:

Date/Time to Plug: 09/21/2007 10:00 AM

Plug Co. License No.: 33961

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: JEFF L. MORRIS

Company: CHEROKEE WELLS LLC

Phone: (620) 378-3650

Proposed Plugging Method: RUN 1' POLY PIPE TO BRIDGE IN HOLE AT 178'. PUMP CEMENT THRU POLY PIPE TO FILL HOLE FROM BOTTOM TO TOP. CUT OFF PLOY PIP AND LEAVE IN HOLE AFTER CEMENT IS CURED, CUT OFF ALL PIPE APPROX. 3' BELOW GROUND LEVEL.

Plugging Proposal Received By: ALAN DUNNING

Witness Type: NONE

Date/Time Plugging Completed: 11/09/2007 12:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

The operator reported that the location was not accessible with a pulling unit. Therefore a 1" poly pipe was lowered down hole to 178'. The well was pumped full of cement thru this cement string. A total of 15 sacks of 60/40 poz mix with 2% gel were used to plug well. The well was cut off below plow depth.

Perfs:

Top	Bot	Thru	Comments
190	236		
INVOICED			
DATE <u>9/15/08</u>			
INV. NO. <u>2009060348</u>			
RECEIVED			
KANSAS CORPORATION COMMISSION			
AUG 25 2008			
CONSERVATION DIVISION WICHITA, KS			

RECEIVED
KCC DISTRICT #3

AUG 6 2008

CHANUTE, KS

AMD

Remarks:

Plugged through: TBG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

PK