

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22229-00-00  
Spot: SENE Sec/Twnshp/Rge: 7-35S-13W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: STERNBERGER Well #: 3  
County: BARBER Total Vertical Depth: 4965 feet

Operator License No.: 3532  
Op Name: CMX, INC.  
Address: 1551 N WATERFRONT PKWY STE 150  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3980		WITH 2 SX CMT
CIBP		4140		
PROD	5.5	4963	2800	
SURF	8.625	371		

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2008 9:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4830' WITH 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 30' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/20/2008 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3980' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID CASING DOWN & RAN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT (200# HULLS IN W/GEL & 50# HULLS IN W/CMT). 2ND PLUG AT 390' WITH 50 SX CMT (50# HULLS IN W/CMT). 3RD PLUG AT 30' WITH 15 SX CMT.

Perfs:

INVOICED  
DATE 9/15/08  
INV. NO. 2009060349

RECEIVED  
KANSAS CORPORATION COMMISSION


AUG 27 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed \_\_\_\_\_

*Stephen J. Pfeifer*  
(TECHNICIAN)

Form CP-2/3