

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02983-00-01
Spot: SENESE Sec/Twnshp/Rge: 5-8S-17W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: ECKERT Well #: 2
County: ROOKS Total Vertical Depth: 3388 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY STE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3385	0	w/100 sxs cmt
SURF	8.625	108	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2008 10:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING, CO. Phone: (713) 209-1110

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 200# hulls - 13 sxs gel spacer.
Operator trying to workover well - hit old 5 1/2" casing at 1000'.
Operator only able to retrieve approximately 200' of new 5 1/2" casing.

110-11

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2008 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

08/19/2008
Ran tubing to 2696' - pumped 13 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel.
08/25/2008
Pulled 200' of 5 1/2" casing - ran tubing to 1000' - pumped 240 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing and topped off well with 20 sxs 60/40 pozmix - 4% gel.

Perfs:

INVOICED
DATE 9/15/08
INV. NO. 2009060358

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 28 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #32876.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

AUG 26 2008

PKS

V. D. SIDNEY #2 ECKHART 5-8-17W 22
SE NE SE

Contr. _____ ROOKS County

E. 1930 RR Comm. _____ Comp. 12-26-52 IP 169 BOPD
PERM. PMP.

Tops	Depth	Datum
ARR	3384	-1454
T.D.	3387	-1457

Casing
8" 108
5" 3385

LONE STAR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS