

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00888-00-00
Spot: NESWSW Sec/Twnshp/Rge: 20-16S-1W
1011 feet from S Section Line, 4385 feet from E Section Line
Lease Name: HUNTER Well #: 3
County: SALINE Total Vertical Depth: 2676 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2665		
SURF	10.75	102		

86.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2008 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING INC Phone: (620) 587-3361

Proposed Plugging Method: PERFORATE PIPE @250' BELOW SURFACE PIPE. SAND BOTTOM TO 50' ABOVE PERFS AND CAP WITH 5 SXS CEMENT. RUN TUBING TO 250' AND CIRCUALTE CEMENT TO SURFACE.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2008 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

RAN TUBING TO 2480' AND PUMPED 50 SXS CEMENT TO PLUG BOTTOM. PULLED TUBING TO 270' AND PUMPED 115 SXS TO CIRCULATE TO SURFACE.

Perfs:

INVOICED
DATE 9/15/08
INV. NO. 2009060351

Remarks: COPELAND CEMENTING TICKET #C33502 TOTAL = 165 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed Meg Eves
(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PKT