

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00890-00-00
Spot: NENESW Sec/Twnshp/Rge: 20-16S-1W
2326 feet from S Section Line, 3073 feet from E Section Line
Lease Name: A A HUNTER Well #: 1
County: SALINE Total Vertical Depth: 2685 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2665		
SURF	10.75	102		

87.26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2008 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 10 SXS CEMENT. RUN TUBING TO 250' AND CIRCULATE TO SURFACE WITH CEMENT.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2008 2:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

PREFORATED PIPE AT 250'. RAN TUBING TO 2528' AND PUMPED 50 SXS CEMENT. PULLED TUBING TO 270' AND PUMPED 70 SXS CEMENT TO CIRCULATE TO SURFACE. PUMPED 20 SXS TO BRING TO BACKSIDE (CASING ANNULUS) TO SURFACE.

Perfs:

INVOICED
DATE 9-15-08
INV. NO. 2009060351

Remarks: COPELAND CEMENTING TICKET #C33500. TOTAL = 140 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Greg Eves

(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

AKS