

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20200-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 20-16S-1W  
344 feet from S Section Line, 4413 feet from E Section Line  
Lease Name: HUNTER Well #: 5  
County: SALINE Total Vertical Depth: 2700 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 1822 24TH STREET  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2698		175 SX
SURF	8.625	210		200 SX

87.75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2008 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 50' ABOVE PERFS AND CAP WITH 5 SXS CEMENT. PERFORATE PIPE AT 250'. RUN TUBING TO 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/28/2008 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

RAN TUBING TO 2550' AND PUMPED 35 SKS CEMENT. PULLED TUBING TO 270' AND PUMPED 250 SXS CEMENT (DID NOT CIRCULATE) QUIT FOR WEEKEND. 4/28 PUMPED 70 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:

**INVOICED**  
DATE 9-15-08  
INV. NO. 2009060351

Remarks: COPELAND CEMENTING TICKET #C33504 TOTAL = 355 SXS 60/40 POZ 4% GEL  
Plugged through: TBG

District: 02

RECEIVED  
KANSAS CORPORATION COMMISSION

Signed Meg Eves  
(TECHNICIAN)

SEP 02 2008

CONSERVATION DIVISION  
WICHITA, KS

*PA*