

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20310-00-00
Spot: SWNESW Sec/Twnshp/Rge: 20-16S-1W
1678 feet from S Section Line, 3809 feet from E Section Line
Lease Name: HUNTER Well #: 6
County: SALINE Total Vertical Depth: 1930 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1911		100 SX
SURF	7	204		67 SX

73
62. ~~510~~

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2008 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: PERFORATE PIPE @ 50' BELOW SURFACE PIPE. SAND BOTTOM TO 50' ABOVE BOTTOM PERFS AND CAP WITH 4 SXS CEMENT. RUN TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2008 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:
PERFORATED PIPE AT 254'. RAN TUBING TO 1790' AND PUMPED 35 SXS CEMENT. PULLED TUBING TO 270' AND PUMPED. 70 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:
INVOICED
DATE 9-15-08
INV. NO. 2009060351

Remarks: COPELAND CEMENTING TICKET #C-33501 TOTAL = 110 SXS. 60/40 POZ 4% GEL
Plugged through: TBG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION
Signed Greg Eves (TECHNICIAN)

SEP 02 2008
CONSERVATION DIVISION
WICHITA, KS

Handwritten initials