

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-27232-00-00
Spot: S2SESE Sec/Twnshp/Rge: 4-28S-15E
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: PIERPOINT FARMS Well #: A-7
County: WILSON Total Vertical Depth: 655 feet

Operator License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: 4916 CP BOWIE BLVD STE 204
FT WORTH, TX 76107

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------|
| SURF | 8.625 | 50 | | 75 SX CMT. |

35

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/08/2007 10:00 AM
Plug Co. License No.: 33072 Plug Co. Name: WELL REFINED DRILLING COMPANY, INC.
Proposal Rcvd. from: JEFF MORRIS Company: CHEROKEE WELLS LLC Phone: (620) 212-4089

Proposed Plugging Method: WELL IS 6.75" OPEN HOLE - SURFACE CASING DID NOT SEAL AND LEAKED AROUND PIPE. CEMENT SQUEEZE WAS ATTEMPTED - NO SUCCESS. CLEAN OUT W/6.75" BIT TO TD OF 655'. PUMP CEMENT THRU DRILL STEM FROM TD TO SURFACE. LET CEMENT CURE FOR 72 HRS THEN CUT OFF CASING 3' BELOW SURFACE.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 08/31/2007 12:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The well was cleaned to 655' with hammer bit. A 2.375" cement string was lowered to 650' and the well was then filled from btm to top thru this cement string. A total of 165 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored

RECEIVED
KCC DISTRICT #3

AUG 25 2008 AMD

CHANUTE, KS

INVOICED

DATE 9-15-08
INV. NO. 2009060353

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 29 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

PH