

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-25297-00-01
Spot: NESWNW Sec/Twnshp/Rge: 6-33S-15E
3800 feet from S Section Line, 4490 feet from E Section Line
Lease Name: WRIGHT II Well #: 7 F
County: MONTGOMERY Total Vertical Depth: 1223 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.85	1223		
SURF	7	20		

39.75

Well Type: EOR UIC Docket No: E23534.25 Date/Time to Plug: 07/09/2008 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: COLT ENERGY Company: COLT ENERGY Phone: (620) 365-3111

Proposed Plugging Method: CLEAN OUT OLD WELL TO TD AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 5:00 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

WASHED WELL TO 1223, RAN 1" TO 1142', PUMPED 50 SACKS FROM TD TO SURFACE. PULLED 1" OUT OF WELL AND HOOKED TO 2 7/8" AND PRESSURED TO 700 PSI AND SHUT IN. 50 SACKS OF 60/40 POZ MIX CEMENT WITH 4% GEL USED.

Perfs:

RECEIVED
KCC DISTRICT #3

AUG 27 2008

CHANUTE, KS

INVOICED
DATE 9-15-08
INV. NO. 2009060354

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 29 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through:

District: 03

Signed

Russell Hine by BL
(TECHNICIAN)

PKT