

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22387-00-00  
Spot: NENW Sec/Twnshp/Rge: 17-15S-22W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: SARGENT Well #: 1  
County: TREGO Total Vertical Depth: 4220 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4216	0	150/200 SX CMT.
SURF	8.625	219	0	160 SX CMT. <u>137.15</u>
T1	2.875	4180		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/05/2008 8:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: ARNOLD HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 4% gel - 300# hulls - 15 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2008 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 219' w/160 sxs cement.  
5 1/2" production casing set at 4216' w/150 sxs cement.  
TD 4220'. PBTd 4208'. DV Tool at 1620' w/200 sxs cement.  
Ran tubing to 4171' - pumped 15 sxs gel followed with 40 sxs cement with 150# hulls.  
Pulled tubing to 1700' - pumped 165 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 15 sxs cement.  
Connected to 8 5/8" surface casing - pumped 15 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4212	4214		
4198	4204		

**INVOICED**  
DATE 9/15/08  
INV. NO. 2009060362

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 22 2008**

Remarks: SWIFT SERVICES, INC.-TICKET #14817.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

*PKT*

Form CP-2/3

**AUG 13 2008**

HESS OIL CO  
 MCPHERSON KS 67460

HESS OIL CO  
MCPHERSON KS 67460

17-15S-22W  
750' FNL & 1990' FWL, SEC

#1 SARGENT

site: 8 N & 3 W OF BROWNELL KS	op: TREGO	API 15-195-22387
contr: MALLARD JV #1	field: GSL EXT (5/8 W; INFLD DISC)	
op: JAMES C. HESS		
fr date: 08/29/2006	spc date: 09/19/2006	d1g comp: 09/25/2006
	card issued: 03/05/2007	last revised: 03/05/2007


ELV: 2286 KB, 2281 GL SMP
tops.....depth/datum
ANH.....1651 +635
B/ANH.....1691 +595
HEEB.....3636 -1350
LANS.....3677 -1391
STARK.....3891 -1605
BKC.....3943 -1657
MARM.....3970 -1684
PAW.....4041 -1755
FT SC.....4122 -1836
CHER SH.....4145 -1859
PBTD.....4208 -1922
RTD.....4220 -1934
NO LOG

IP status:  
 OIL, P 7 BOPD, NW, CHER SD 4198-4204, 11/08/2006  
 CSG: 8-5/8" 219 / 160 SX (ALT 2), 5-1/2" 4216 / 350 SX  
 COMMENT: PROPOSED START 09/11/2006; MI & RURT  
 9/19/2006  
 NO CORES  
 DST (1) 4145-4220 (CHER), / 30-45-30-45, (1ST OP) WB BLDG  
 TO SB OFF BTM BKT/20', (2ND OP) WB BLDG FB 10 INCH,  
 REC 560' TF: 65' OCMW (3% OIL, 77% W, 20% M), 185' HMC  
 GSY OIL (10% G, 80% OIL, 10% M), 185' HMCO (80% OIL,  
 20% M), 125' OCM (30% OIL, 70% M) ISP 1220# FSP 1191#  
 IFP 24# -208# FFP 196# -265# IHP 2020# FHP 1924#

COPYRIGHT 2008  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)