

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

21847

API Well Number: 15-015-27802-00-01
Spot: NWNW KCC-NR Sec/Twnshp/Rge: 19-26S-3E
~~4720~~ feet from S Section Line, ~~4720~~ feet from E Section Line
~~4876~~
Lease Name: PHANNENSTIEL Well #: 2
County: BUTLER Total Vertical Depth: 3304 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3296 225 SX CMT
SURF Size: 8.625 feet: 205 100 SX CMT

\$107³⁸

Well Type: ~~SWD~~ SWD UIC Docket No: _____ Date/Time to Plug: 07/22/2004 12:30 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: R. A. SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Bottom plug -- Sand back to 2812'; dump bail 5 sxs; shoot and pull pipe.
Top plug -- Run tubing to 255'; circ cement to surface.

RECEIVED
KCC DISTRICT #2
JUL 23 2004
WICHITA, KS

Plugging Proposal Received By: BILL JOHNSON Witness Type: NONE
Date/Time Plugging Completed: 07/22/2004 2:30 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Bottom plug -- Sanded back 2812' and dumped bail 5 sacks of cement.
Top plug -- Ran 1-1/2" tubing to 270' and circulated cement to surface.
130 sacks of 60/40 posmix with 4% gel.
Inspected site at 4:00 pm; cement to surface.
Site located west of Phannenstiel #1, approximately 200'.

Perfs:

Top	Bot	Thru	Comments
2862	2863		


RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 2004
7-28-04
CONSERVATION DIVISION
WICHITA, KS

Remarks: TOP PLUG -- COPELAND ACID #24940

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 7-29-04
INV. NO. 2005060232