

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 009-20,476 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3-6-1970

Well Operator: PYRAMID CORPORATION INC KCC License #: 5617
(Owner / Company Name) (Operator's)

Address: 1030 VINCENT LN City: WICHITA

State: KS Zip Code: 67206 Contact Phone: (316) 685-9695

Lease: PASCOE A Well #: 2 Sec. 11 Twp. 19S S. R. 15W East West

NW SW SW Spot Location / QQQQ County: BARTON

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 895' Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 3540' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3540-55'

Elevation: 1943 (G.L. / K.B.) T.D.: 3555 P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): ACCORDING TO THE RULES AND REGULATIONS

OF THE STATE OF KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

SEP 08 2008

If not explain why? _____ CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: MIKE KELSO

Phone: (620) 938-2943

Address: P O BOX 467 City / State: CHASE KS 67524

Plugging Contractor: MIKE KELSO OIL CORP KCC License #: 31528
(Company Name) (Contractor's)

Address: SAME AS ABOVE Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): as soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/5/08 Authorized Operator / Agent: Mike Kelso
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dist 4
PKT*

W E L L L O G

DATE COMMENCED: February 16, 1970
 DATE COMPLETED: February 25, 1970

Pyramid Corporation, Inc.
 PASCO A-2
 100' N of NW SW SW
 Sec. 11-T19S-R15W
 Barton County, Kansas

ELEVATION 1943 K.B.

0 - 150' Surface Clay & Red Clay
 150 - 310' Sand & Shale
 310 - 430' Shale
 430 - 883' Sand-Shale-Red Bed
 883 - 915' ANHYDRITE
 915 - 1865' Shale - Shells
 1865 - 2235' Lime & Shale
 2235 - 2645' Shale
 2645 - 2829' Shale & Lime
 2829 - 3156' Lime
 3156 - 3159' Shale
 3159 - 3170' Shale & Lime
 3170 - 3184' Lime
 3184 - 3234' Shale
 3234 - 3244' Lime - Shale
 3244 - 3459' Lime
 3459 - 3481' Shale
 3481 - 3532' Conglomerate
 3532 - 3555' Sand
 3555' RTD

FORMATION DATA

ANHYDRITE	883
HEEBNER	3156
TORONTO	3170
DOUGLAS	3184
BR. LIME	3234
LANSING	3244
BASE LANSING	3459
CONGLOMERATE	3481
REAGEN SAND	3532
RTD	3555

SURFACE PIPE: Set new 20#
 8-5/8" casing at 895' with
 160 sks. Halco light & 125
 sks. Pozmix

PRODUCTION STRING: Set used
 5 1/2" pipe at 3540' with 125 salt
 saturated pozmix.

RECEIVED
 KANSAS CORPORATION COMMISSION

SEP 08 2008

CONSERVATION DIVISION
 WICHITA, KS

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the
 facts and statements herein contained are true and correct to the
 best of his knowledge.

Subscribed and sworn to before me this 26th day of February 1970
 My Commission Expires

Larry Curtis



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

THE PYRAMID CORPORATION, INC.
1030 VINCENT ST
WICHITA, KS 67206-1350

September 10, 2008

Re: PASCOE A #2
API 15-009-20476-00-00
11-19S-15W, 990 FSL 4950 FEL
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 9, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550