

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1978
8-14-78
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Charles Caelock

Complete Address 1515 Hillcrest Rd. Newton, Ks. 67114

Lease Name Wait Well No. #2

Location CN $\frac{1}{2}$ -SW-SW Sec. 3 Twp 26 Rge. 3 (E)

County Butler Total Depth 2830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling

Address 2809 King Hutchinson Ks. 67501 License No. 440

Operation Completed: Hour 11:20 AM Day 10 Month 8 Year 78

The above well was plugged as follows:

8 $\frac{5}{8}$ " sur. csg. 200' / 200 sx cent. T.D. 2830'

5 $\frac{1}{2}$ " csg. 2795' / 80 sx cent.

Bottom plug - Sand 2830' to 2790' / 55x cent.

Shot 5 $\frac{1}{2}$ " csg. at 2286' pulled same. Left 509' 5 $\frac{1}{2}$ " csg. in hole

Top Plug - Set 15' Rock Bridge 230' to 215', Redi mix to

4' below sur. 3yds. Redi Mix. cent.

I hereby certify that the above well was plugged as herein stated.

Signed: Alan Thompson
Well Plugging Supervisor

INVOICED
DATE 8-14-78
INV. NO. 5421-E