

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
REV. 1-68  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1979  
8-28-79  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -015 - 21136-00-00 (of this well)

Operator's Full Name Dunbar + Son Oil Enterprises, Inc.  
Complete Address R.R. #3 Box 252-A Winfield, Ks 67156  
Lease Name Riley Well No. #1  
Location C NW NE Sec. 4 Twp 26-S Rge. 3 (E) 00  
County Butler Total Depth 2733'  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Towanda Well Service, Inc.  
Address Box 337 Towanda, Ks 67042 License No. \_\_\_\_\_  
Operation Completed: Hour 3:00 PM Day 24 Month 8 Year 1979

The above well was plugged as follows:

8 5/8" 200' - circ/cent - 4 1/2" csg. 2727'  
Perf. 2276" to 2279'  
Set rock + sand bridge 2260' to 2250' / 5 ex cent  
Ripped + pulled 1823' 4 1/2" csg. left 904' csg in hole  
Set 10" rock bridge 215"  
Filled hole / 4 yds redi-mix to 2' below sur.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Thompson  
Well Plugging Supervisor

DATE 9-7-79  
INV. NO. 6588-F