




STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Butler County, Sec. 12 Twp. 26-S Rge. 3 (E) (W)
Location as "NE/CNW%SW%" or footage from lines C W/2 W/2 NW
Lease Owner Oilfield Supply & Trading, Inc.
Lease Name Depew Well No. 1
Office Address 430 Greenwood, Wichita, Kansas 67211
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 10 1970
Application for plugging filed 10-23 1970
Application for plugging approved 10-26 1970
Plugging commenced 10-30 1970
Plugging completed 11-2 1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ted E. Dewey
Producing formation Mississippi Depth to top 2753 Bottom 2755 Total Depth of Well 2755 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------------|------------------------|-------------|-------------|---------------|-------------|--------------|
| <u>Mississippi</u> | <u>oil & water</u> | <u>2753</u> | <u>2755</u> | <u>8-5/8"</u> | <u>200'</u> | <u>None</u> |
| | | | | <u>4-1/2"</u> | <u>2753</u> | <u>2300'</u> |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Load hole with water - sand went to 2735 - dump 4 sax cement - shoot @ 2390 & 2289 - pull 30 joints pipe.

Pull 43 joints 4 1/2" pipe - total 2300 ft. - bail hole to 220 ft. - rock bridge to 200 ft. - dump 3 yds ready mix cement to surface - tear down.

RECEIVED
STATE CORPORATION COMMISSION
12-2-70
DEC 2 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock
Address 320 North Park, Stafford, Kansas 67578

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, W. R. Justice, (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Justice
W. R. Justice
430 Greenwood, Wichita, Kansas 67211
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of November, 19 70

My commission expires May 14, 1972

Ethel Spicer
Ethel Spicer



TRIANGLE DRILLING

324 North Orchard

EL DORADO, KANSAS

To Oil Field Supply and Trading Inc.

Invoice No. _____

430 Greenwood

Date _____

Wichita, Kansas

For Month Of _____

Lease Depay

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1975
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

| | | |
|------|-------|-------------------------|
| 0 | ----- | 10 Clay and Soil |
| 40 | ----- | 193 Shale and Lime |
| 193 | ----- | 760 Lime and Shale |
| 760 | ----- | 975 Shale |
| 975 | ----- | 1565 Shale and Lime |
| 1565 | ----- | 2751 Lime and Shale |
| 2751 | ----- | 2755 Lime, Miss. R.T.F. |