

15-065-20619-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company  
Complete Address 617 Union Center, Wichita, Kansas.  
Lease Name Meinershagen Well No. 1  
Location CN/2-N/2-NW Sec. 22 Twp. 10 Rge. (E) (W) 24  
County Graham Total Depth 3800'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Above  
Address      License No.       
Operation Completed: Hour 10:00 AM Day 10 Month 7 Year 1973

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 950'.  
      
Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement  
thru DP from 1175' to 850'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.  
      
    

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 7/13/73  
INV. NO. 7630-W