

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beacon Resources Corporation,

Complete Address 1000 Century Plaza, Wichita, Kansas.

Lease Name Kline Well No. 1

Location S/2-NE-SW Sec. 22 Twp. 10 Rge. (E) (W)24

County Graham Total Depth 3990'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address Box #352, Russell, Kansas. License No.

Operation Completed: Hour 6:00 AM Day 5 Month 1 Year 1972

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
from 1125' to 800'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4970-W