

15-065-20287-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten initials*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,  
Complete Address 617 Union Center Building, Wichita, Kansas.  
Lease Name Knoll Well No. 1  
Location NW-NW-SE Sec. 16 Twp. 10 Rge. (E) (W) 24  
County Graham Total Depth 4045'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Above  
Address \_\_\_\_\_ License No. \_\_\_\_\_  
Operation Completed: Hour 12:15 PM Day 7 Month 12 Year 1969

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 965'.  
Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru  
DP from 1200' to 875'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from  
240' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 12/11/69  
INV. NO. 1016-44