

15-065-20431-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,
Complete Address Box #370, Hays, Kansas.
Lease Name J. Sproul Well No. 3
Location NE-NE-SW Sec. 2 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 4040'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dreiling Oil, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 11:45 AM Day 5 Month 5 Year 1971

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with--
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement
thru DP from 1200' to 875'. Pulled DP to 215' and displaced 25 Sx. cement thru DP
from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/12/71
INV. NO. 3664-11