

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Sproul Well No. B-1

Location Appr:-CW/2-SE-SW Sec. 2 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4075'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address P. O. Box #261, Great Bend, Kansas. License No.

Operation Completed: Hour 8:30 AM Day 23 Month 11 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mdd. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Pichels*
Well Plugging Supervisor

DATE 12/2/69
INV. NO. 956-W