

15-065-20429-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name O. Nickelson Well No. 4

Location NE-SW-NW Sec. 2 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4045'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Allied Cementing Company, Incorporated,

Address Box #207, Russell, Kansas. License No.

Operation Completed: Hour 1:00 PM Day 16 Month 9 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'. (This well temporarily abandoned).

Squeezed well thru surface casing initially with 5 sacks hulls and 5 sacks gel and
followed with 100 Sx. cement from 1225' to 900' then 17 sacks gel from 900' to 220'
and followed with 25 Sx. cement from 220' to 145' then 3 sacks gel from 145' to 25'
and finally 10 Sx. cement from 25' to bottom of cellar. Maximum pump-in pressure--
300#. Final shut-in pressure--100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-22-71

INV. NO. 4363-W

Signed: M. L. Nichols
Well Plugging Supervisor