

15-065-20428-00-00

Form CP-3
Rev. 6-4-68

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Nickelson Well No. 3

Location NE-SE-NW Sec. 2 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4100'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 2:30 PM Day 28 Month 10 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated.

4100'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 4071'. Top perforations from 3914' to 3918'.

Pushed plug to 3875', sanded well back to 3850' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 100 Sx. cement from 1085' to 760' then 15 sacks gel from 760' to 160' and finally 50 Sx. cement from 160' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-150#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/2/71
INV. NO. 4573-W

Signed: *W. L. Nichols*
Well Plugging Supervisor