

15-065-20407-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt,
Complete Address Drawer #370, Hays, Kansas.
Lease Name O. Nickelson Well No. 1
Location SW-SW²NW Sec. 2 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 4048'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated _____
Plugging Contractor L. J. Dreiling & Sons, Incorporated,
Address R. R. #2, Victoria, Kansas. License No. _____
Operation Completed: Hour 12:00 M Day 20 Month 12 Year 1970

The above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 100 Sx. cement thru
DP from 1625' to 1300'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 12/27/71
INV. NO. 3144-11