

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation,

Complete Address 312 Union Center Building, Wichita, Kansas.

Lease Name Gano Well No. 3

Location CS/2-SE Sec. 2 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4056'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks License No.

Operation Completed: Hour 4:00 AM Day 2 Month 7 Year 1969

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 186'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/69

INV. NO. 80-W

Signed: W. L. DeChale
Well Plugging Supervisor