

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20379-00-00
20279-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1969

CONSERVATION DIVISION
Wichita, Kansas

12-29-69

KCC
apb.

Operator's Full Name Aspen Drilling and Black Petroleum, Inc.

Complete Address Wichita, Kansas

Lease Name Whisman "D" Well No. 1

Location S/2 S/2 SW Sec. 3 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Aspen Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:30A Day 27 Month 12 Year 1969

The above well was plugged as follows:

RTD 3640' 8 5/8 csg set at 249' cwc 165 sk. Cmt. Mat. 50-50 poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hullsand 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/29/69

INV. NO. 1165-W

Signed: Lia F. Massey
Well Plugging Supervisor