


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 16 Twp. 10S Rge. 24 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Kansas Petroleum, Inc.
Lease Name KNOLL Well No. #1
Office Address 500 Insurance Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5, 1975
Application for plugging filed October 5, (verbally) 1975
Application for plugging approved October 5, (verbally) 1975
Plugging commenced October 5, 1975
Plugging completed October 5, 1975
Reason for abandonment of well or producing formation No commercial quantity
of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4025' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 217' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug Set @ 1050' with 70 sx. cement
2nd Plug Set @ 200' with 40 sx. cement
3rd Plug Set @ 140' with 10 sx. cement
Plug Was down @ 9:30 p.m. October 5, 1975

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr-Exec. V.P. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)



Subscribed and Sworn to before me this 13th day of October, 1975
July 21, 1979
Sandra Russell
Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:
GEOLOGIST:
SPUD DATE:
COMPLETION DATE:

Kansas Petroleum, Inc.
Abercrombie Drilling, Inc.
KNOLL #1
NW NW SW Section 16-10S-24W
Graham County, Kansas
Dick Roby
September 30, 1975
October 5, 1975

| | | |
|------|------|---------------------|
| 0 | 224 | Clay & Sand & Shale |
| 224 | 566 | Sand & Shale |
| 566 | 1150 | Shale |
| 1150 | 1158 | Sand, Pyritic |
| 1158 | 1170 | Shale and Anhydrite |
| 1170 | 1450 | Shale |
| 1450 | 2034 | Shale & Sand |
| 2034 | 2107 | Shale |
| 2107 | 2142 | Anhydrite |
| 2142 | 3178 | Shale |
| 3178 | 3818 | Shale & Lime |
| 3818 | 4025 | Lime |
| | 4025 | Rotary Total Depth |

Drilled 220' of 12 1/2" hole. Set 5 jts. of 8 5/8" casing @ 217'K.B. with 165 sx. Quick Set cement. Cement circulated. Plug was down @ 2:00 p.m. September 30, 1975. Plugged and Abandoned: 1st Plug Set @ 1050' with 70 sx. cement; 2nd Plug Set @ 200' with 40 sx. cement; 3rd Plug Set @ 40' with 10 sx. cement. State Plugger: Gilbert Balthazor Plug was down @ 9:30 p.m. October 5, 1975.

SAMPLE TOPS:
Anhydrite 2108'
B/Anhydrite 2142'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)


Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KNOLL #1, NW NW SW, Section 16-10S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of October, 1975.

Sandra Russell
Sandra Russell-Notary Public



My Commission Expires: July 21, 1979

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1975

CONSERVATION DIVISION
Wichita, Kansas