

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 16 TWP. 10 RGE. 24 E/W  
Location as in quarters or footage from lines:  
SW SE NE


Lease Owner Energy Three Inc.  
Lease Name State Well No. 1  
Office Address Box 1505, Great Bend, Ks 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): dry  
Date Well Completed 1-23-83  
Application for plugging filed 1-23-83  
Plugging commenced 1-23-83  
Plugging completed 1-23-83  
Reason for abandonment of well or producing formation dry

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mike Balazore

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4065'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.


plugged w/190 sx 50-50- pos 6% gel  
went in hole w' plugging stands set plug #1 @ 2134 w/ 20 sx  
2nd plug @ 1250' w/ 100 sxs  
3rd plug @ 260' w/ 40 sxs  
4th plug @ 40' w 1/2 sx hulls & 10' sx cement 10 sx in mousehole  
10 sx in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied cementing

STATE OF Kansas COUNTY OF Russell, ss.  
Tim Scheck (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Timothy F. Scheck  
Box 52, Gorham, Ks 67640  
(Address)



SUBSCRIBED AND SWORN TO before me this 31st day of January, 19 83



My Commission expires: January 19, 1985

Joan Weigel  
Notary Public.

# BIG THREE Drilling, Inc.

Tim Scheck, President  
Larry Langhofer, Tool Pusher

DRILLING SERVICES TO 5,000 FEET IN KANSAS AREA

South Clifford, Box 52  
Gorham, Kansas 67640

Company	Energy Three Inc.
Farm	State #1
Location	SW SE NE 16-10-24W
County	Graham
Contractor	Big Three Drilling Inc.
Comm	1-17-83
Compl	1-23-83
Total Depth	4065' R.T.D.
Casing	Dry
Production	Dry

Figures Indicate Bottom of Formation

Sand & Top Soil	255'
Red Bed	345'
Shale	1115'
Sand & Shlae	2075'
Anhydrite	2113' to 2166'
Shale	2525'
Sand & Shale	3005'
Shale & Lime	4065'

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Big Three Drilling Inc.

*Timothy F. Scheck*

Timothy F. Scheck

STATE OF KANSAS  
FEB 7 1983  
REGISTRATION DIVISION  
Wichita, Kansas