

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,709-00-00

LEASE NAME Leo Dinkel

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from ^N Section Line

1,320 Ft. from ^W Section Line

SEC. 16 TWP. 10 RGE. 24 (E) or (W)

COUNTY Graham

LEASE OPERATOR Staab Energy & Leasing

ADDRESS 2514 Haney Drive, Hays, Ks. 67665

PHONE#(913) 628-1326 OPERATORS LICENSE NO. 3655

Date Well Completed 5-31-93

Character of Well D & A

Plugging Commenced 5-31-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-31-93

The plugging proposal was approved on 5-31-93 (date)

by Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,037'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	220'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,145' thru drill pipe. Push bridge plug to 1,250', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 270', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 180 5655 ^{RT} _{KCC}

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Energy & Leasing

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of all facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665


SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 93

Ruth Phillips

Notary Public

My Commission Expires:





Shields


15-065-22709-00-00

Russell, Kansas

WELL LOG

Operator: Staab Energy & Leasing
 Well: Leo Dinkel #1
 Commenced: May 24, 1993
 Completed: May 31, 1993
 Contractor: Shields Drilling Co.

Well Description: N/2 N/2 NW/4
 Sec. 16-10S-24W
 Graham County, KS.



Elevation: 2,489' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	220'	Cmtd. w/150 sax

..... Figures Indicate Bottom of Formations

Shale	30'
Shale & sand	223'
Shale	895'
Shale & sand	2,130'
Anhydrite	2,165'
Shale	2,543'
Shale & lime	3,808'
Lime	4,037' RTD

Notes

RECEIVED STATE CORPORATION COMMISSION

JUN 10 1993

CONSERVATION DIVISION
Wichita, Kansas