

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

15-065-01905-00-03

Lease Operator: Berexco, Inc. Address: PO Box 723 Hays, KS 67601 Phone: (785) 628-6101 Operator License #: 5363 Type of Well: OIL EOR Docket #: E21996 The plugging proposal was approved on: 11-29-07 by: MARVIN MILLS Is ACO-1 filed? No If not, is well log attached? No Producing Formation(s): L-KC Depth to Top: 3855 Bottom: 3964

API Number: 15-065-01905-00-01 Lease Name: GRA-SHER Well Number: M1 Spot Location (QQQQ): NE - NE - SW - Feet from 2312 North / South Section Line 2970 - 3010 East / West Section Line Sec. 6 Twp. 10 S. R. 25 East West County: GRAHAM Date Well Completed: 9-59 Plugging Commenced: 11-29-07 Plugging Completed: 11-29-07

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: L-KC, OIL, 0, 193, 8-5/8, 9-59, ---. Row 2: 0, 4032, 4-1/2, 9-59, ---.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


TIH WITH 2-3/8 BX WORKSTRING #37 RUN TBG TO 2580' TOP OF FISH IS 2606 MIX 285' 60/40 4% WITH GOOD RETURNS. CMT COLORED WATER PULL TBG TO 1470' PMP 125 SKS 60/40 4% GEL WITH 500# HULLS. CMT CIRC TOH WITH TBG. SQZ ANOTHER 20 SKS DOWN 4-1/2" CSG. TIE ONTO ANNULUS AND PUMP 50 SKS, SHUT IN AT 200 PSI

Name of Plugging Contractor: Berexco, Inc. License #: 5363 Address: PO Box 723 Hays, KS 67601

Name of Party Responsible for Plugging Fees: Mark Leiker w/ Berexco, Inc. State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature] (Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 17 day of December, 20 07. Shanna Miller, My Commission Expires: 9/19/09 Notary Public

RECEIVED KANSAS CORPORATION COMMISSION DEC 26 2007 CONSERVATION DIVISION WICHITA, KS

Handwritten notes: KCC 12/26/07, PS 12/26/07

Handwritten initials/signature