

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Quinque Operating Company

Address: 908 N.W. 71st St., Oklahoma City, OK 73116

Phone: (405) 840-9876 Operator License #: 5225

Type of Well: Injection Docket #: E-28094  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/12/08 (Date)

by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Swope Depth to Top: 4833 Bottom: 4866 T.D. 5200

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 119210570001

Lease Name: Crooked L

Well Number: 1-21A

Spot Location (QQQQ): SW/4 nwsW

1440 Feet from  North /  South Section Line

4912 Feet from  East /  West Section Line

Sec. 21 Twp. 32 S. R. 28  East  West

County: Meade

Date Well Completed: 8/27/01

Plugging Commenced: 7/21/08

Plugging Completed: 7/22/08

KCC DISTRICT AGENT

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	60	20	20	0
		0	1066	8 5/8	1066	0
		0	5091	4 1/2	5091	1170

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls mud. Set 4-1/2" CIBP at 4777'. Loaded hole with mud. Shot casing at 1170'. Laid down same.

TIH with tubing. Pumped 50 sacks of cement at 1170'. TOH to 540'. Pumped 50 sacks of cement.

TOH to 33'. Pumped 10 sacks of cement to surface.

Name of Plugging Contractor: Phil Dollar Oilfield Services, Inc. License #: 33311

Address: P.O. Box 744, Perryton, TX 79070

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Quinque Operating Company

State of Oklahoma County, Oklahoma, ss.

SEP 2 2008

Catherine Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**KELLY FREEMAN**  
Notary Public  
State of Oklahoma  
Commission # 06007471 Expires 08/01/10

(Signature) Catherine Smith

(Address) 908 N.W. 71st St., Oklahoma City, OK 73116

SUBSCRIBED and SWORN TO before me this 28th day of August, 20 08

Kelly Freeman My Commission Expires: 08/01/10  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*