

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: AX&P, Inc. 67301
Address: P.O. Box 1176, Independence, KS
Phone: (620 325 5212) Operator License #: 3830
Type of Well: old Producer Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-9-08 (Date)
by: Alan Dunning (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Neodesha Sd. Depth to Top: 770 Bottom: 790 T.D. 815

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-205-19571-00-00
Lease Name: Unit 1 - Cramer
Well Number: Cramer #2
Spot Location (QQQQ): SWNEENE
350 Feet from North / South Section Line
490 Feet from East / West Section Line
Sec. 32 Twp. 30 S. R. 16 East West
County: Wilson
Date Well Completed: 5/25/63
Plugging Commenced: 5-10-08
Plugging Completed: 6-5-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	800'	2"	800'	460'
		0	740'	6 1/4"	740'	0
		0	35'	12"	35'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH 460' of 2" pipe (pipe broke off) ; RIH with 1" pipe to 455'; spotted 14 sx cement. POH 1"; Perforated @460' (2shots); 175'(2); 40' (2 shots) for a total of 6 shots. RIH w. 1" pipe to 450'; cemented to surface w. 100 sx cement. POH 1" and topped off hole
Total cement used: 114 sx.

Name of Plugging Contractor: AX&P, Inc. License #: 3830 RECEIVED KANSAS CORPORATION COMMISSION
Address: P.O. Box 1176, Independence, KS 67301 AUG 11 2008
Name of Party Responsible for Plugging Fees: AX&P, Inc. CONSERVATION DIVISION
State of Kansas County, Wilson, ss. WICHITA, KS

Jurgen J. Hanke (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

BECKY R. HAMBLETON
Notary Public - State of Kansas
My Appt. Expires

(Signature) Jurgen J. Hanke
(Address) 20147 200 Rd. Neodesha, KS 66757

SUBSCRIBED and SWORN TO before me this 8th day of August, 2008
Becky R. Hambleton My Commission Expires: 8/27/09
Notary Public