

769

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1966
8-4-66

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name La-Ro-Bee Ind. Co. Inc.

Complete Address: 5301 N. Broadway - Wichita, Kans.

Lease Name Blue- Well No. 1

Location NW-NW-NE Sec. 16 Twp. 26 Rge. 3 (E) (W)

County Butler Total Depth 2807

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: a new Rotary hole. Pipe was set - well tested - failed to produce.

Plugging Contractor: Glint Eng. & Const. Co.

Address: El Dorado Kans. License No. 547

Operation Completed: Hour 5:00 Day 2 Month 8 Year 1966

The Above well was plugged as follows:

Filled hole with Rock to 2780 ft.
Mixed & dumped 5 sacks Cement.
Pulled 2490 ft. of 5 1/2" casing.
Set a 15 ft. Rock Bridge at 200 ft.
Added 20 sacks Cement.
Mudded hole from this Point to 30 ft.
Added 10 sacks Cement to surface.
(200 ft. of 10 3/4" surface Pipe - Circulated.)

I hereby certify that the above well was plugged as herein stated.

Bill Anderson

Signed: Paul Turpin
Well Plugging Supervisor

INVOICED

DATE 8-4-66
INV. NO. 4784-E