

Handwritten initials

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,
 Complete Address Box #553, Russell, Kansas.
 Lease Name McPherson Well No. A-3
 Location CS/2-SW-NE Sec. 4 Twp. 9 Rge. (E) (W) 23
 County Graham Total Depth 3764'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated _____
 Plugging Contractor Knight Casing Pulling Company, Incorporated,
 Address Box #405, Chase, Kansas. License No. 624
 Operation Completed: Hour 2:15 PM Day 13 Month 2 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 125 Sx.
3764'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back. Top perforations from 3750' to 3747'.
Pushed plug to 3600', built sand bridge to 3550' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 16 sacks gel and followed with 100 Sx. cement from 1000' to 675' then 11 sacks gel from 675' to 235' and followed with 25 Sx. cement from 235' to 160' then 3 sacks gel from 160' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--
200#. Final shut-in pressure--100#. (Mudding and cementing by Halliburton).
(Recovered 2900' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dickel*
Well Plugging Supervisor

INVOICED

DATE 2/16/70
INV. NO. 1435-W