

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
2-16-70
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name McPherson Well No. A-2
Location CNW-SE Sec. 4 Twp. 9 Rge. (E) (W) 23
County Graham Total Depth 3825'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #405, Chase, Kansas. License No. 624
Operation Completed: Hour 11:30 AM Day 13 Month 2 Year 1970

The above well was plugged as follows:

229'--8 5/8" Surface casing, cement circulated.

3823'--5 1/2" Production casing, no information of cement on bottom nor plug backs.

Top perforations from 3714' to 3719'.

Ran 2" tubing to bottom of well and displaced 25 Sx. cement thru Tubing. Let cement
set and pulled 5 1/2" casing then squeezed well with initially 5 sacks hulls and 15 sacks
gel then 100 Sx. cement from 1000' to 675' then 11 sacks gel from 675' to 235' and
followed with 25 Sx. cement from 235' to 160' then 2 3 sacks gel from 160' to 40'
and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-
300#. Final shut-in pressure--150#. (Mudding and cementing by Halliburton).
(Recovered 1160' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 2/16/70INV. NO. 1434-W