

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1970
2-19-70
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name McPherson Well-No. A-9

Location NE-NE-SE Sec. 4 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 4250'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas License No. 624

Operation Completed: Hour 1:00 PM Day 13 Month 2 Year 1970

The above well was plugged as follows:

???-8 5/8" Surface casing, cement circulated.
4220'--5 1/2" Production casing cemented on bottom with 250 Sx. and thru DV Tool set in the Anhydrite with 450 Sx. Well Plugged back to 3734'. Top perforations @ 3704'.
Pushed plug to 3500', sanded back to 3470' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing (148') and squeezed well initially with 16 sacks gel and followed with 100 Sx. cement from 1000' to 175' then 3 sacks gel from 175 to 45' and finally 15 Sx. cement from 45' to bottom of cellar. Final shut-in pressure-250#. Final shut-in pressure 100#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 2/19/70
INV. NO. 1461-W