

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-9-70
JUL 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dane G. Hansen Trust

Complete Address Logan, Kansas 67646

Lease Name Staggers Well No. 1

Location SW NE NW Sec. 5 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3875

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:30P Day 8 Month 7 Year 1970

The above well was plugged as follows:

RTD 3875' 8 5/8 csg set at 206' cwc Cmt Mat 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe, Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lawrence Massey
Well Plugging Supervisor

INVOICED
DATE 7/9/70
INV. NO. 2194-W