

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1974  
3-7-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Casey Jones Well No. 5

Location NE-SW-NE Sec. 11 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3858'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 5:45 PM Day 2 Month 3 Year 1974

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 165 Sx.

3850'--5 1/2" Production casing cemented on bottom with 200 Sx. Open hole completion.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with

110 Cu. Ft. cement from 950' to 625' then 10 sacks gel from 625' to 225' and followed

with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and

finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure-

-150#. Final shut-in pressure-50#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 3/12/74

INV. NO. 8735-W