

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham
Location: Se-Se-Nw Sec. 11 Twp. 9 Rge. 23 (E) (W)
Name of Field: _____ Total Depth: 3864

I have this date completed supervision of plugging of:

Lease Name: Peckham Well No. 1
Operator's Full Name: Murphy Dry Co.
Complete Address: 617 Union Center - Wichita Kans.
Plugging Contractor: C. Woods
Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5:30 P.M. Day 12 Month June Year 1961

The above well was plugged as follows:

Depth - 3864 - 8 5/8 set at 210' - 5 1/2" set at 3864 - Top Pipe - 3774 to 3795
Sand to 3764 and dumped 5 sac cement with dump bailer
shot 5 1/2 at 2600' and pulled same out of hole. Filled
hole with mud to 205' built rock bridge and displaced
25 sac cement, chunk mud to 45' built rock bridge
and 10 sac cement. Cemented to base of cellar.

Signed: Robert P. Leiker
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 6/28/61
INV. NO. 3317-W

RECEIVED
STATE CORPORATION COMMISSION
6-21-61
JUN 21 1961
CONSERVATION DIVISION