

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1961
7-19-61
CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham
Location: NE NE SW Sec. 11 Twp. 9 Rge. _____ (E) _____ (W) 23
Name of Field: _____ Total Depth: 3814

I have this date completed supervision of plugging of:

Lease Name: Jones Well No. B-1
Operator's Full Name: Murfin Drg Co
Complete Address: 617 Union Center Wichita, Kansas
Plugging Contractor: same & Sun Cementing Co
Company Tools
Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 15 Month 7 Year 61

The above well was plugged as follows:
10 3/4" 215' circulated with cement - 7" 3814' with 100 sax cement. PB to
3768' - perforated 3768' - filled with sand to 3770', set 6 sax cement
with dump bailer - pulled 1500' 7" to 590' - pumped 60 sax gel mud - pulled
7" to 500' and spotted ~~30~~ 25 sax cement through 7" - heavy mud to 160'-
displaced 20 sax cement through 7" at 160' - heavy mud to 35', set bridge and
filled to bottom cellar with cement.
Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/9/61
INV. NO. 3555-W