

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1974
3-7-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Casey Jones Well No. 3

Location SW-SW-NE Sec. 11 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 11:00 AM Day 2 Month 3 Year 1974

The above well was plugged as follows:

226'--8 5/8" Surface casing, cement circulated with 175 Sx.
3857'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug-back indicated.

Pushed plug to 3450', sanded well back to 3420' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 110 Cu. Ft. cement from 975' to 650' then 10 sacks gel from 650' to 250' and followed with 30 Cu. Ft. cement from 250' to 175' then 4 sacks gel from 175' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickels
Well Plugging Supervisor

DATE 3/12/74
INV. NO. 8734-W