

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-21-71
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,
Complete Address Drawer #370, Hays, Kansas.
Lease Name C. Jones Well No. 2
Location SW-NW-NE Sec. 11 Twp. 9 Rge. (E) (W) 23
County Graham Total Depth 3872'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #405, Chase, Kansas License No. 624
Operation Completed: Hour 11:30 AM Day 17 Month 6 Year 1971

The above well was plugged as follows:

164'--8 5/8" Surface casing, cement circulated.
3864'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3850'. Top perforations from 3820' to 3800'.
Sanded well back to 3778' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 100 Sx. cement from 1000' to 675' then 13 sacks gel from 675' to 175' and followed with 25 Sx. cement from 175' to 100' then 2 sacks gel from 100' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-350#. Final shut-in pressure-150#. (Mudding and cementing operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6/22/71
INV. NO. 3887-u