

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas
11-15-1971

15-065-30139-00-01

Operator's Full Name Beacon Resources,
Complete Address 1000 Century Plaza, Wichita, Kansas.
Lease Name McElroy Well No. 1
Location SE-NW-NE Sec. 4 Twp. 10 Rge. (E) (W) 22
County Graham Total Depth 3860'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated WASHDOWN
Plugging Contractor Sage Drilling Company, Incorporated,
Address 500 Bitting Building, Wichita, Kansas License No.
Operation Completed: Hour 9:00 AM Day 8 Month 11 Year 1971

The above well was plugged as follows:

228'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

W. S. Nichols
Well Plugging Supervisor

DATE 11-15-71

INV. NO. 4650-W