

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20404-00-00

01-13-1971

Operator's Full Name Beacon Resources Corporation,

Complete Address 1000 Century Plaza, Wichita, Kansas.

Lease Name McElroy Well No. 1

Location SW-NE-NE Sec. 4 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 5 Month 1 Year 1971

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 760'.

Circulated hole with heavy mud. Pulled DP to 985' and displaced 100 Sx. cement thru
DP from 985' to 660'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Dichek
Well Plugging Supervisor

INVOICED

DATE 1-13-71
DIV. NO. 3206 W