


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 4 Twp. 9S Rge. 23W (E) (W)
Location as "NE/CNWxSWx" or footage from lines SE SE NW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Brown "C" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 7, 1955
Application for plugging filed December 15, 1960
Application for plugging approved December 17, 1960
Plugging commenced January 9, 1961
Plugging completed January 11, 1961
Reason for abandonment of well or producing formation Commercial quantities
of oil depleted.
If a producing well is abandoned, date of last production 42,332 Blots 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	Not pulled
				5-1/2"	3845'	" "

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast on location. Checked hole.
Sanded back to 3730' mixed and run 3 sacks
cement with dump bailer. Cleaned out cellar.
Took tension on pipe. Worked pipe and made
shots at 1460'-1400'-1304'-1200' loose at
1200' pulled 30 jts. Pulled 7 jts. pipe for
total of 37 jts. Cleaned hole. Mudded back
to 250' set 10' rock bridge with 25 sacks
cement by dump bailer. Mud to 40' set
10' rock bridge with 10 sack cement to base
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1961

2-6-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company-
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. L. Bacon (employee of owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) BY: R. L. Bacon V-P

780 Fourth National Bldg., Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of February, 1961

Cecilia C. Klug
Cecilia C. Klug Notary Public.

My commission expires October 24, 1962



DRILLER'S LOG

Imperial Drilling Company, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Brown "C" No. 1
(Christie Brown No. 1)
SE SE NW Sec. 4-9S-23W
Graham County, Kansas

Total Depth: 3845'

Commenced: February 25, 1955 Completed: 3-7-55 Elevation: 2286' R.B.
Production: 1155 BOPD
No Water

Contractor: Imperial Drilling Company, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 250' W/175 sacks cement.
Set 5-1/2" Casing at 3845' W/125 sacks cement.

Figures indicate bottom of formation:

Sand, Rock and Shell (Hard)	130'		<u>TOPS</u>	
Sand and Shale	250'			
Shell and Shells	685'	Anhydrite	1922'	(-364)
Shale, and Sand (Hard)	1220'	Heebner	3564'	(-1278)
Hard Sand	1340'	Lansing	3605'	(-1319)
Shale and Shells	1440'	Rotary Total Depth	3845'	(-1559)
Dakota Sand	1680'			
Shale and Shells	1922'			
Anhydrite (Medium)	2035'			
Shale and Shells	2395'			
Shell and Shells	2565'			
Shale and Lime (Ft. Riley)	2575'			
Lime and Shale	3537'			
Lime	3845'			
Rotary Total Depth	3845'			

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1961
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling report.

IMPERIAL DRILLING COMPANY, INC.

By: [Signature]
Vice President

Subscribed and sworn to before me this 25th day of March, 1955.

My commission expires:

November 9, 1957

[Signature]
Notary Public