

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Brush Creek Unit

WELL NUMBER 3 101

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 4 TWP. 9S RGE. 23W (E) or (W)

COUNTY Graham

Date Well Completed 4-21-55

Plugging Commenced 11-10-92

Plugging Completed 11-17-93

LEASE OPERATOR John J. Darrah Jr.

ADDRESS 412 East Douglas, Wichita, Kansas 67202

PHONE# (316) 263-2243 OPERATORS LICENSE NO. 5088

Character of Well input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-10-92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? N/A

Producing Formation Lansing Depth to Top 3470 Bottom 3799 T.D. 3851

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing "H"	3740-43	surface	228'	8 5/8	228'	none
Lansing "K"	3795-99	surface	3851	5 1/2	3851	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Shot pipe at 1900', 1080', 600'. Ran 2 3/8" tbg to 3200', pumped away plugs while pulling tubing. Used 315 sax 65/35 cement w/ 10% gel in casing and on backside. 215 sax in casing and 100 sax in backside. Finished job with 200# on casing and on backside.

Name of Plugging Contractor B/J Titan License No. unknown

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah Jr.

STATE OF Kansas COUNTY OF Ellis, ss.

Employee of Operator (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Philip Mast


(Address) Ellis, KS

SUBSCRIBED AND SWORN TO before me this 25th day of May 1993

Helen J. Beecher Notary Public

My Commission Expires: 2-11-94

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88