

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20622-00-00  
LEASE NAME Fountain B  
WELL NUMBER 1  
3300 Ft. from S Section Line  
990 Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202  
PHONE # ( ) 267-3241 OPERATORS LICENSE NO. 30606  
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 1 TWP. 5S RGE. 23W (E) or (W)  
COUNTY Graham  
Date Well Completed 3/30  
Plugging commenced 11/06/95  
Plugging Completed 11/06/95

The plugging proposal was approved on \_\_\_\_\_ (date)  
by \_\_\_\_\_ (KCC District Agent's Name).  
Is ACO-1 filed? No If not, is well log attached? No  
Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ TD \_\_\_\_\_  
Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put	Pulled out
				8 5/8	211	
				5 1/2	3865	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.


Perforated 5 1/2" csg @ 1940' & 1120'. Tied onto 5 1/2" csg. Pumped 275 sx 60/40 Poz, 10% gel, 300# hulls. Max press 100 psig. ISIP 100 psig. Tied onto 8 5/8" csg, pumped 50 sx 60/40 Poz, 10% gel, 100# hulls. Max press 100 psig. ISIP 100 psig. JC 1:30 p.m. Cemented to surface. Cut off & capped.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606  
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.  
Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M. Jack  
(Address) Wichita, KS



SUBSCRIBED AND SWORN TO before me this 13 day of Nov., 1995  
KERRAN REDINGTON  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appl. Exp. 2/6/98  
My Commission Expires: 2/6/98

Kerran Redington  
Notary Public - Kerran Redington